BRUHAT BANGALORE MAHANAGARA PALIKE

BILL OF QUANTITIES (BOQ)

Name of Work: Providing Drinking Water Works in Ward No. 10 (Doddabommasandra), Vidyaranyapura Sub Division.

Sl. No.	Approved Qty.	Description	Unit	Issued to Technical Manager , KRIDL	
				In Figures	In Words
1	1780	Earthwork excavation for pipeline trenches including deporiting or bank up to a lead of 50 mtrs including shiriry and statting danger lighting and using site rails and boming poles at every 100 mtrs wherever necessary as directed in th following strructure manhole. **Hard Soil**	cum	188.00	Rupees One Hundred Eighty Eight Only
2	2605.00	Providing and instalation at site of works P.V.C.Pipes including cost of pipes and specials and incluidng lowring into trenches, laying true to line, level and perfect linking at joints, leak proof including jointing encasing the pipe alround to a depth Not less than 15cm with grave or selected earth avalabile from the execavation Etc., **75 mm dia 6 KSC PVC pipe**	Rmtr	157.00	Rupees One Hundred Fifty Seven Only
3	1779.75	Refilling the basement and pipeline treanches with secleted available earthe for trench excavation including authority condition in layers from thedi including disponsary of the sunplus earth with a heavy 200 mtrs	cum	61.00	Rupees Sixty One Only
4	1500.00	Providing and fixing Chorinated Poly Venyl Chloride (CPVC) pipes conforming to IS 15778, having thermal stability for hot and cold water supply including all CPVC plain and brass threaded fittings including fixing the pipe with clamp at 1.00 mtr spacing. This includes jointing of pipes and fittings with one step CPVC solvent cement and testing of joints complete. (internal work exposed on wall) - 20mm nominal OD pipes	m	143.10	Rupees One Hundred Forty Three and Ten Paise Only
5	25.00	KSRB 13.6.3-6 : Providing and fixing in position brass gate valve with C.I wheel of approved quality (screwed end) **50mm** nominal bore including cost of all materials, labour and HOM of equipments with all leads complete as per specifications.	Each	2120.00	Rupees Two Thousand One Hundred Twenty Only

1. The work should be executed as per the specification and standard specified by the PWD & Other specifications of the Bangalore Mahanagara Palike and as directed.
2. The work should be carried out as per the directions and instructions of the concerned Engineer
3. The Contractor should maintain the quality of work as per the standard specifications.

28/06

Executive Engineer (Byatarayanapura)
Bruhath Bangalore Mahanagara Palike

I am prepared to take up the above work at the rates quoted by me in the Schedule 'B'. 28/06

CONTRACTOR

EXECUTIVE ENGINEER-4
KRIDL, BBMP DIVISION
BENGALURU-560 010